

Test Hole Data  
Performed by Doane-Collins Eng.  
10/10/95

TH 13-1  
0 - 5" Topsoil  
5 - 32" Sandy loam subsoil  
32 - 68" Coarse sand & gravel, moist with cobbles  
68 - 84" Fine to medium, grey sand with little silt, moist  
No ledge observed  
No groundwater observed  
Mottling observed at 88"

TH 13-2  
Ledge observed at 36"

TH 13-3  
0 - 4" Topsoil  
4 - 32" Sandy loam subsoil  
32 - 68" Coarse sand & gravel, damp  
68 - 84" Very fine, grey, silty sand  
No ledge observed  
Groundwater observed at 78"  
Mottling observed at 23"

TH 13-4  
0 - 7" Topsoil  
7 - 26" Sandy loam subsoil  
26 - 55" Coarse sand & gravel  
55 - 80" Fine to medium, brown sand with little silt  
No ledge observed  
Groundwater observed at 76"  
Mottling observed at 21"

TH 13-5  
0 - 6" Topsoil  
6 - 22" Silty loam subsoil  
22 - 80" Fine, grey silt & silty sand mix  
No ledge observed  
Groundwater observed at 70"  
Mottling observed at 13"

Percolation Test  
Performed by Doane-Collins Eng.  
4-11-00  
Percolation rate = 6.7 min/in

Primary  
SANTARY SYSTEM DESIGN CRITERIA:  
Proposed 3 bedroom house  
Percolation rate = 6.7 min/in  
Required effective leaching area = 490 sf  
Provide 12 inch galleries  
Provide 1 line 48 ft  
1 line 48 ft  
88 ft x 9.9 sf/ft = 519.2 sf required  
Provide 1,000 gallon septic tank  
Provide 180 x 2 reserve area

Minimum Leaching System Spread (MLS)  
d = 23' x = 0.5 ft/ft  
HF = 34  
PF = 1.2  
FF = 1.5  
MLS required = 34 x 1.2 x 1.5 = 61.2 ft  
MLS proposed = 88 ft

Reserve  
Provide 2 lines 64 ft each of 12 inch shallow galleries  
2 x 64 ft x 9.9 sf/ft = 755.2 sf provided

Minimum Leaching System Spread (MLS)  
d = 21' (TH 13-4) x = 176-172/62 = 064 ft/ft  
HF = 34  
PF = 1.2  
FF = 1.5  
MLS required = 34 x 1.2 x 1.5 = 61.2 ft  
MLS proposed = 64 ft


NOTE:  
A pump will be required should the reserve area be utilized.

DATE	REVISION	CK.
04/11/00	GENERAL REVISIONS	

- NOTES:
- No large capacity tube (>100 gallon capacity) are planned and will not be permitted in the proposed residential installation.
  - No garbage grinder installation is planned for the proposed residence. Should a garbage grinder be installed the proposed septic tank shall be increased to the next larger size.
  - No well currently exist within 75 ft of proposed sanitary system.
  - No sanitary system exist within 75 ft of proposed well.
  - All solid piping after the septic tank to be 4" PVC ASTM D 3034, SDR 35.
  - Filter fabric shall be selected from the following table:
- | MANUFACTURER                   | ITEM NUMBER                        |
|--------------------------------|------------------------------------|
| AMERICAN ENGINEERING FABRICS   | AEF-480                            |
| CARTHAGE MILLS                 | W35                                |
| CULTEC                         | 410                                |
| ENGINEERING SYNTHETIC PRODUCTS | TNS 8000                           |
| WEBAF                          | 65304 (4" WIDE)<br>65303 (3" WIDE) |
| BRADLEY INDUSTRIAL TEXTILE     | PHOENIX                            |
| TERRA TEX                      | 301.5<br>P91.5                     |
| TYPAR                          | 3151<br>3201                       |
- No deviation from this plan will be allowed without the approval of the Engineer and Sanitarian.
  - The well location shown herein has been selected to demonstrate compliance with the requirements set forth in the Connecticut Public Health Code and does not imply that this location will produce the appropriate quantity or quality of water.
  - Septic tank construction joints shall be sealed with sealant cement. All pipe connections to the septic tank and distribution boxes shall be sealed with a polyethylene gasket (poly-tak or approved equal).
  - Septic tank baffles shall conform to Section 18-1 TECHNICAL STANDARDS of the State Health Code.
  - Septic tank shall be two compartment tank with heavy duty steel handles for manual access covers not to be installed on outlet piping.

- CONSTRUCTION SEQUENCE (SANITARY SYSTEM)
- Notify Town Health Department and the Engineer 24 - 48 hours prior to the beginning of construction for inspection.
  - Place synthetic barrier as shown on the drawing and in the detail.
  - Remove all trees stumps and deleterious material from system area. Stockpile topsoil for reuse. Do not stockpile topsoil in sanitary system area.
  - Engineer to field stake well and septic system prior to construction.
  - Strip area for system to the gravel layer beneath the subsoil. Approx. 20" (25 inches).
  - Prepare area to be inspected by the Sanitarian or Engineer before placing fill.
  - Place fill to the horizontal and vertical limits shown.
  - Select fill material shall meet criteria set forth below and in the Connecticut Public Health Code:
    - Select fill material placed within and adjacent to proposed leaching area shall be composed of clean sand and gravel, free from organic matter and foreign substances. The fill material shall meet the following requirements unless otherwise approved by a professional engineer for use within the leaching area:
      - The fill shall not contain any material larger than three (3) inches.
      - Up to 45 percent of the dry weight of the representative sample may be retained on the #4 sieve (This is the gravel portion of the sample).
      - The material that passes the #4 sieve is then reweighed and the sieve analysis started. The remaining sample shall meet the following gradation criteria:
 

Sieve Size	Percent Passing
#4	100 percent
#10	70% - 100 percent
#40	10% - 80 percent (see Note below)
#100	0% - 20 percent
#200	0% - 5 percent
      - Percent Passing the #40 sieve can be increased to no greater than 75 percent if the percent passing the #100 sieve does not exceed 10 percent and the #200 sieve does not exceed 5 percent.
  - The responsibility for the preparation of a leaching area utilizing inert material is that of the licensed installer. The installer shall take the necessary steps to protect the underlying naturally occurring soils from over-compaction and saturation once exposed.
    - Fill placement must be supervised by the Engineer and the Sanitarian.
    - Testing may be required to assure fill quality.
  - Install septic system as shown.
    - If soil conditions other than those shown in the soil logs are encountered during the installation of the sanitary system, the Design Engineer or the Sanitarian shall be notified and the work will be halted pending review of those conditions. If necessary the sanitary system may be revised.
    - A minimum of 4 feet must be maintained between the bottom of the system and ledge. A minimum of 1.5 feet must be maintained between the bottom of the system and seasonal high groundwater.
    - The sanitary system shown herein must be constructed to the horizontal and vertical alignment shown, unless expressly directed by the Engineer in writing and with the approval of the Town Health Department.
  - Do not backfill any portion of the sanitary system until inspected by the Engineer and the Sanitarian and until the Engineer has completed a RECORD survey.
  - Replace topsoil, grade, seed and mulch all disturbed areas.
  - Maintain synthetic filter barrier until all disturbed areas are stabilized.




Test Hole Data  
Performed by Angus McDonald/Gary Sharpe & Assoc.  
7-7-87

TH 204  
0 - 6" Topsoil  
6 - 26" Silty loam  
26 - 55" Red/brown, silty sand & gravel  
Ledge observed at 55"  
Mottling observed at 25"  
Groundwater observed at 45"

TH 205  
0 - 10" Topsoil  
10 - 39" Fine, sandy loam with silt  
39 - 48" Brown, sand & gravel  
Ledge observed at 48"  
No groundwater observed  
No mottling observed

- EDGE OF WATER/STREAM
- EXISTING CONTOURS
- PROPOSED CONTOURS
- FLAGGED WETLANDS LINE
- SILT FENCE
- BUILDING SETBACK LINE
- T.H. TEST HOLE



Notice to Lot Owner:  
Activity within 60 ft of the wetlands or within 100 ft of the water course other than that which is shown hereon is limited to maintenance of existing vegetation and does not include removal or deposition of substantial amounts of material. Refer to Town of Essex, Inland Wetlands and Water Courses Commission Regulations.

REFERENCE MAP:  
"Site Development Plan and Sedimentation & Erosion Control Plan, Woodwind, prepared for Pratt-Read Corporation, Main Street (Ivoryton) Essex, Connecticut".  
Scale 1"=40', Date 5/9/89. Prepared by Angus McDonald/Gary Sharpe & Associates, Inc., Old Saybrook, Ct.

FILE COPY

map 39  
Lot 1-13

ROBERT L. DOANE JR.  
CONN. P.E. & L.S. LIC. NO. 11463

APPROVED

NOV 28 2001

STATE OF CONNECTICUT  
ROBERT L. DOANE JR.  
No. 11463  
LICENSED PROFESSIONAL ENGINEER

STATE OF CONNECTICUT  
ROBERT L. DOANE JR.  
No. 11463  
LICENSED LAND SURVEYOR

DOANE-COLLINS ENGINEERING ASSOCIATES  
CIVIL ENGINEERING & LAND SURVEYING  
P.O. BOX 113 CENTERBROOK, CT. 06409 (860)767-0138

SITE PLAN  
LOT # 13  
WOODWIND SUBDIVISION  
ESSEX, CT.

SCALE: 1"=40'  
DATE: 03/14/00  
SHEET NO.: 1 OF 1  
IDENT. NO.: E-787-46