


RECEIVED
 MAR 16 2017
 BY:

PADELLI RESIDENCE
 IVORYTON, CT

**WETLAND/WATERCOURSE LANDSCAPE
 IMPACT REVITALIZATION DESIGN PLAN**

SCALE: 1/8" = 1'

DESIGNED BY: SARAH BURRILL-MANCO
 Ivoryton, CT 06442
 860.510.1438
 greenspacegardendesign@gmail.com



Test Hole Data
Performed by Doane-Collins Eng
10/18/95

TH 13-1
0 - 2" Topsoil
2 - 32" Sandy loam subsoil
32 - 68" Coarse sand & gravel, moist with clabbles
68 - 84" Fine to medium, gray sand with little silt
No ledge observed
No groundwater observed
Mottling observed at 68"

TH 13-2
Ledge observed at 36"

TH 13-3
0 - 4" Topsoil
4 - 32" Sandy loam subsoil
32 - 68" Coarse sand & gravel, damp
68 - 84" Very fine, gray, silty sand
No ledge observed
Groundwater observed at 78"
Mottling observed at 25"

Percolation Test
Performed by Doane-Collins Eng
4-11-95

Percolation rate = 6.7 min/in

Primary
SANTARIY SYSTEM DESIGN CRITERIA
Proposed 3 bedroom house
Percolation rate = 6.7 min/in
Requires effective leaching area = 495 sq ft
Provide 16 inch galleries

Minimum Leaching System Spread (M.L.S.S.)
d = 25 + 0.5 ft
M.L.S.S. required = 34 x 1.2 x 1.5 = 61.2 ft
M.L.S.S. proposed = 88 ft

Reserve
Provide 2 lines 64 ft each of 12 inch shallow galleries
2 x 64 ft x 1.8 ft of IF = 753.2 sq ft provided

Minimum Leaching System Spread (M.L.S.S.)
d = 21 (7th 13-4) x = 176-172.82 = 84 ft

M.L.S.S. required = 74 x 1.2 x 1.5 = 61.2 ft
M.L.S.S. proposed = 84 ft

NOTE:
A pump will be required should the reserve area be utilized.

DATE	REVISION	CK
04/11/00	GENERAL REVISIONS	

- NOTES:
- No large aggregate (4" - 100 gallon capacity) are planned and will not be permitted in the proposed residence.
 - No garbage disposal installation is planned for the proposed residence. Should a garbage disposal be installed the proposed septic tank shall be increased to the next larger size.
 - No wells currently exist within 75 ft of proposed sanitary system.
 - No sanitary systems exist within 75 ft of proposed well.
 - All solid piping other than water lines shall be 4" PVC (ASTM D 3034, SDR 35).
 - Filter fabric shall be selected from the following table:

MANUFACTURER	ITEM NUMBER
AMERICAN ENGINEERING FABRICS	AZF-402
CANTONIA WELLS	W02
CELESTIC	411
ENGINEERING SYNTHETIC PRODUCTS	19E R022
WELBY	45304 (4 WELBY) 45305 (4 WELBY)
BRADLEY INDUSTRIAL TEXTILE	PHOENIX
TERMA TEX	2015 2016
TYLAR	2017 2021

- No deviation from this plan will be allowed without the approval of the Engineer and Sanitarian.
- The well location shown herein has been selected in accordance with the requirements of the Connecticut Public Health Code and does not imply that this location will produce the appropriate quantity or quality of water.
- Septic tank construction shall be in accordance with applicable codes. All pipe connections to the septic tank and distribution system shall be made with polypropylene (poly) pipe (not approved pipe).
- Septic tank baffles shall conform to Section 19-1 TECHNICAL STANDARDS of the State Health Code.
- Septic tank shall be two compartment tank with heavy duty steel handles for manhole access covers and gas baffles installed on outlet piping.


CONSTRUCTION SEQUENCE (SANTARIY SYSTEM)

- Notify Town Health Department and the Engineer 24 - 48 hours prior to the beginning of construction for inspection.
- Place existing barrier as shown on the drawing and in the plan.
- Remove all trees, shrubs and other vegetation material from system area. (Thinkage signal for trees to not be removed in sanitary system area.)
- Engineer to field check well and septic system prior to construction.
- Site area for system in the gravel layer beneath the subsoil. (As per 19-1-32 code.)
- Prepared area to be inspected by the Sanitarian or Engineer before placing fill.
- Place fill to the horizontal and vertical limits shown.
- Inspect fill material shall meet criteria set forth below and in the Connecticut Public Health Code (see 19-1-32 code) and approved by the Engineer and Sanitarian. The fill material shall meet the following requirements unless otherwise approved by a professional engineer for use within the working area:
 - The fill shall not contain any material larger than three (3) inches.
 - Up to 45 percent of the dry weight of the representative sample shall be retained on the #4 sieve (that is the gravel portion of the sample).
 - The material that passes the #4 sieve or that is rejected shall be the same material as that of the remaining sample shall meet the following gradation criteria:

Sieve Size	% Retained
#4	0% percent
#10	10% percent
#20	10% percent (see Note below)
#40	10% percent
#60	0% percent
#100	0% percent

NOTE: Percent passing for #40 sieve can be increased to no greater than 75 percent if the percent passing the #100 sieve does not exceed 10 percent and the #200 sieve does not exceed 5 percent.

- The responsibility for the preparation of a leaching area extends, when material is that of the landowner, to the landowner. The landowner shall take the necessary steps to protect the underlying capacity occurring due to over-compaction and saturation over exposure.
- The placement must be supervised by the Engineer and the Sanitarian.
- Testing must be required to ensure fill quality.
- If any conditions other than those shown in the plan are encountered during the installation of the sanitary system, the design Engineer or the Sanitarian shall be notified and the work will be halted pending review of those conditions. If necessary, the sanitary system shall be revised.
- A minimum of 4 feet shall be maintained between the bottom of the system and edge. A minimum of 1.5 feet must be maintained between the bottom of the system and stream bed groundwater.
- The sanitary system shown herein shall be constructed in the horizontal and vertical alignment shown, unless expressly directed by the Engineer in writing and with the approval of the Town Sanitarian.
- Set out backfill and portion of the sanitary system shall be approved by the Engineer and the Sanitarian and until the Engineer has completed a RECORD survey.
- Replace legal grade seed and mow all disturbed areas.
- Maintain synthetic fiber barrier until all disturbed areas are stabilized.




Test Hole Data
Performed by Angus McDonald/Gary Sharpe & Assoc.
7-7-97

TH 204
0 - 6" Topsoil
6 - 26" Silty loam
26 - 55" Red, heavy, silty sand & gravel
Ledge observed at 55"
Mottling observed at 25"
Groundwater observed at 45"

TH 205
0 - 10" Topsoil
10 - 39" Fine sand, loam with silt
39 - 40" Brown, sand & gravel
Ledge observed at 40"
No groundwater observed
No mottling observed

- 100 --- EDGE OF WATER/STREAM
- 100 --- EXISTING CONTOURS
- 100 --- PROPOSED CONTOURS
- 50 --- FLAGGED WETLANDS LINE
- 50 --- SILT FENCE
- 50 --- BUILDING SETBACK LINE
- T.H. TEST HOLE



Notice to Lot Owner:
Activity within 60 ft of the wetlands or within 100 ft of the water course other than that which is shown herein is limited to maintenance of existing vegetation and does not include removal or disposition of substantial amounts of material. Refer to Town of Essex, Inland Wetlands and Water Courses Commission Regulations.

REFERENCE MAP:
"Site Development Plan and Sedimentation & Erosion Control Plan, Woodwind, prepared for Pratt-Read Corporation, Main Street (Ivoryton) Essex, Connecticut", Scale 1"=40', Date 5/9/89, Prepared by Angus McDonald/Gary Sharpe & Associates, Inc., Old Saybrook, Ct.

ROBERT L. DOANE JR.
CONN. P.E. & L.S. LIC. NO. 11463

DOANE-COLLINS ENGINEERING ASSOCIATES
CIVIL ENGINEERING & LAND SURVEYING
P.O. BOX 113 CENTERBROOK, CT. 06409 (860)767-0138

SITE PLAN
LOT # 13
WOODWIND SUBDIVISION
ESSEX, CT.

SCALE	DATE	SHEET NO.	TOTAL NO.
1"=40'	03/14/00	1 OF 1	0001 NO.