



Docko, Inc. *Serving the waterfront community since 1987*

P.O. Box 421, Mystic, CT 06355 (860) 572-8939 Fax: (860) 572-7569, email: office@docko.com

January 18, 2021

Mr. Jeffrey Going
Essex Harbor Management Commission
Essex Town Hall
29 West Ave
Essex, CT 06426

Re: CT DEEP COP Application
46 Crosstrees Hill Rd.

Dear Mr. Going,

This letter is in response to your email dated January 14, 2021 regarding the Bergantino property. The application materials in question are part of the NDDDB application which is the first step in the application process. Thru further discussions with the DEEP and the client, the project has since changed. There will not be any tie- piles, ramps or float installed on this property. The final application project description and construction methodology is as follows:

Project Description:

This proposed project is to remove an existing pier, ramps and floats. Construct a new 4-FT wide wood pile and timber pier with a 5-FT wide x 10-LF "L Shaped" pier head all waterward of the Mean High Tide and CT Coastal Jurisdiction lines.

Construction Methodology:

The new dock facility will be a driven-pile supported, 60+/- LF by 4-foot wide, 29+/-feet of wooden pier will have a 1:10 slope leading to a 5-FT wide x 10-LF "L-Shaped" pier head. The existing pier head was crib supported and that cribbing will be removed. Approximately 9 pairs of piles will be driven with a 10-foot spacing to support the pier. The new dock facility will be constructed slightly shifted to the north at the shoreline landing in order to pass between areas of tidal vegetation south of the existing dock in order to minimize environmental impact.

We trust this information will assist you in completing your review of this project. Please let us know if the need for further information is required. As always, we appreciated your assistance.

Very truly yours,
DOCKO, INC.

Christina Lopes
Project Administrator

JM: cl
Enclosures
cc: CT DEEP LWRD
File: 19-06-3042 BERGANTINO